MOP MODULE « OPERA »



Kit de branchement à assembler PE 100 SDR 11comprenant une prise en charge, un robinet et deux manchons.

Pression de service admissible : 16 bar (eau)





Mise en œuvre à l'aide de la clé DAA



Extension de manœuvre possible Réf : BS-KHP.

eau)				
d1	d2	Référence	Repère de	Poids
(mm)	(mm)	Reference	perçage	(kg)
40	25	90000511	3	1,11
40	32	90000521	3	1,18
50	25	90000611	3	1,17
50	32	90000621	3	1,19
63	25	90004611	3	1,19
63	32	90004621	3	1,26
63	40	90004631	3	1,17
75*	25	90003611	3	1,45
75	32	90003621	3	1,46
75	40	90003631	3	1,43
90	25	90005611	2	1,37
90	32	90005621	2	1,41
90	40	90005631	2	2,45
90*	50	90005641	2	2,12
110	25	90006611	2	1,38
110	32	90006621	2	1,42
110	40	90006631	2	2,67
110*	50	90006641	2	2,17
125	25	90007611	2	1,42
125	32	90007621	2	1,46
125	40	90007631	2	2,50
125*	50	90007641	2	2,66
140	25	90002611	2	1,45
140	32	90002621	2	2,29
140	40	90002631	2	2,49
140*	50	90002641	2	2,74
160	25	90008611	2	1,50
160	32	90008621	2	1,54
160	40	90008631	2	3,26
160*	50	90008641	2	2,12
180	25	90009611	1	1,52
180	32	90009621	1	1,58
180	40	90009631	1	2,91
180*	50	90009641	1	2,18
200	32	90001621	1	1,60
200*	50	90001641	1	2,19
225	25	90001711	1	1,59
225	32	90001721	1	1,56
. , .				

^{*} Avec réduction électrosoudable en sortie de la dérivation.